

ADDENDUM #1

PROJECT: MULTIPLE SITES ROOFING PROJECT (#720-06-2223)

- 1. See attached aerial views of school sites that are part of this project for clarification on location of rooms where the roofs will be replaced.
- 2. Davis HS Scope Clarification Room N1A scope is as follows:
 - Clean and remove debris from roof and gutters.
 - Install 2X4 wood nailer around entire perimeter to match height of new insulation.
 - Fill flutes on existing metal roof with 3" thick flute filler insulation.
 - Install one layer of ½" Dens-Deck over insulation and mechanically fasten to the existing metal roof.
 - Install mechanically fastened 45-Mil TPA single ply roof system.
 - Edge metal will have 4" face and be installed with a continuous cleat.
 - Install new seamless gutters and 24 gauge downspouts.
- 3. DaVinci HS Scope Clarification gutters will be left in place. Drip edge on rake edges will measure 4" and be installed with a continuous cleat.
- 4. North Davis ES Scope Clarification Drip edge on rake edges will measure 4" and be installed with a continuous cleat.
- 5. Cesar Chavez Scope Clarification Include two new Flashco type vents with PVC flange to replace existing vents.
- 6. Emerson Scope Clarification Remove vents and abandoned boiler vent penetration.











